
2008 Solar Annual Review Meeting

Session: (CIGS)

Company or Organization: (The Dow Chemical Company)

Funding Opportunity: (SAI TPP)



Robert J. Cleereman
Sr. Director, BIPV Solar Technology
Dow Building Solutions
989-636-5425
rjcleereman@dow.com



Dow Chemical Company – SAI TPP



Goal: A full line of cost effective PV Containing Building Products

SAI Team Members:

Dow Building Solutions

Fronius

Global Solar Energy

IBIS Associates


Lennar Corporation

Prost Builders, Inc

Pulte Homes, Inc.

University of Delaware - IEC

Southern California Edison



Budget and Solar America Initiative Alignment



Project Start Date: October 1, 2007
FY 2008 Budget: \$ 5.7MM Spent: \$2.3MM
FY 2009 Budget: \$ 6.9MM
FY 2010 Budget: \$ 7.1MM

This project supports the SAI Initiative by providing a route to LCOE grid parity for residential and commercial rooftop PV installations

Planned Work & Accomplishments (Since Project Start - September 2007)



- 1. Evaluated 50+ CIGS Packaging Material Options**
- 2. Designed & manufactured “analog” BIPV shingles**
- 3. Designed pilot line, initiated construction, specified and ordered equipment for 1 MW manufacturing pilot line**
- 4. Purchased and installed extensive suite of testing equipment**
- 5. Built & Installed CIGS Module & Shingle Arrays**

Solar Arrays – Thin Film α -Si - Uni-Solar (Pre-SAI)



Solar Array – Thin Film CIGS (GSE)



GSE CIGS – Modules & Shingles




Module Array

Shingle Array

Example Power Output – 4 Arrays



Overview Monday, April 14, 2008



Planned Work & Accomplishments (Since Project Start - September 2007)



1. Evaluated 50+ CIGS Packaging Material Options
2. Designed & manufactured “analog” BIPV analog shingle
3. Designed pilot line, initiated construction, specified and ordered equipment for 1 MW manufacturing pilot line
4. Purchased and installed extensive suite of testing equipment
5. Built & Installed 1 KW Shingle Array
- 6. Conducted VOC (Voice of Customer) interviews at the National Home Builder’s Show.**
- 7. Conducted phone conference interviews with 15 utility companies in United States**
- 8. Completed market adoption study and scale up feasibility plan**





Forecast the growth of BIPV in residential roofing based on “technical replacement model”

- ✓ Defensible demand forecasts
 - Expressed as power (MW), area (sq-meter), and money (nominal \$)
- ✓ State-wise or regional segmentation
 - Scalable to other regions
- ✓ Rational economic behavior
- ✓ *Bona fide*, citable data sources
- ✓ 30 year horizon, 15 year focus





Market Penetration - Based on four historical substitution analogs:





Fiberglass for organic fiber in asphalt shingles

Architectural for 3-tab shingles in roofing



Devolution of coal in residential heating

High efficiency gas furnaces



Market Adoption Analysis



$$\text{Demand}_t = \text{Technical Potential}_t \times \text{Penetration}_t \times \text{Acceptance}_t$$

- ✓ Technical Potential
 - What is the maximum possible market size, based on physical limitations?
- ✓ Penetration
 - How fast will the market grow, based on historical analogies?
- ✓ Acceptance
 - How widely will it be accepted, based on economic payback?

Each factor varies in time and geography

Computed stepwise year-to-year


- ✓ 2006 baseline year



Comparison of Penetration Models




Incremental Adoption of BIPV in California Four Alternative Penetration Models



Architectural shingles selected as baseline for subsequent analyses




Summary of 3 Key States - Area Values



California dominates demand forecasts due to size, head-start, incentives



Technical Adoption Rate - California




Incremental sales grow with increased acceptance and penetration



The Role of Incentives



BIPV Demand in FL The Role of Incentives in Stimulating Demand



\$4/watt rebates stimulate demand

- ✓ Effective installed system costs drop below \$2/watt in 2021
- ✓ Acceptance grows to 17% of technical market
- ✓ But, State incentives program costs \$650 million/year




Shingle Market



500,000 m² in 2015 = 54,000 Squares

1 Million Squares Represents 1 G-Watt Annual Installation Opportunity



Conclusions



1. BIPV demand will grow
2. Technical potential is large
3. Early Majority potential is enormous
 - ✓ Virtually all houses can support a 3,300 W kit
 - ✓ 1% of Shingle market equals 1.5 gigawatts
4. Market penetration will follow established patterns
 - ✓ 10 to 20 years to get from 10% to 90% penetration



Project Alignment with Technology Roadmap



IBIS Market Adoption Analysis Conclusion:
System Cost and Grid Electricity Price have strongest
effect on Market Growth


Overarching Goal of Dow
Chemical's SAI Project:

Grid Parity!

PV Power Generation



Power generation varies by time of day and time of year, as do grid prices




- ✓ Significant effect on payback period and customer acceptance
- ✓ Advanced metering required to capture PV benefits

Utility Based PV and System Congestion Issues



The Good News - Utility based solar creates power during peak hours



Utility Based PV and System Congestion



The Bad News - Utility based solar creates power during peak hours

Congestion results in an inability to transmit power from a specific point of delivery to a specific point of receipt

- ✓ “High coincidence” results in high transmission costs
- ✓ New transmission infrastructure will be required
 - At least \$317,058 per pole (230 kV, steel pole)
 - 60 kV to 115 kV: \$69,000 per mile
 - 115 kV to 230 kV: \$690,000 per mile
 - 230 kV to 500 kV: \$1,100,000 per mile
 - Substation enhancements: approximately \$830,000
 - Siting new transmission lines is very difficult
 - Enormous right-of-way costs
 - Concern for negative health and environmental impact

Centralized vs. Distributed PV Systems



Centralized – Utility PV



High system “coincidence” - system
“congestion” exacerbated

Distributed – Rooftop PV



Distributed, “rooftop” PV eliminates
transmission issues caused by
“coincidence” and lack of capacity
– equals reduced investment



The Bottom Line –

Traditional Large Scale Renewable Power Generation Systems (Solar PV, Solar Thermal, Wind) all require significant investment in new transmission infrastructure

Distributed PV (roof-top solar) is in place – zero distribution investment penalty

Roof-top Solar has value beyond standard LCOE calculation – 2-4¢/kwh bonus!



SAI TPP Roadmap

1. Reduced “module” cost
2. Reduced installation cost
3. Reduced distribution cost
4. Eliminate transmission infrastructure investment

Project Alignment with Technology Roadmap



Needs

Approach

1. Reduced “module” cost	<ul style="list-style-type: none">✓ Reduced PV Cell cost (CIGS on Stainless Steel – Global Solar)✓ Design for large scale mass production
2. Reduced installation cost	<ul style="list-style-type: none">✓ True BIPV Integration✓ Design for low cost install✓ Design for high reliability, foolproof, easy diagnostic interconnection
3. Reduced distribution cost	<ul style="list-style-type: none">✓ Dow direct channel to market
4. Eliminate transmission infrastructure investment	<ul style="list-style-type: none">✓ BIPV – Rooftop installation – power generated where it’s used

Planned Work & Accomplishments - Obstacles & Resolution



Obstacle: CIGS SAI Partner, Miasole dropped from Program

Resolution: Global Solar agreed to join program

Obstacle: CIGS supply not available from Miasole

Resolution: Global Solar supplying 10% efficient CIGS cells



G L O B A L S O L A R

Planned Work & Accomplishments - Obstacles & Resolution



Obstacle: Most films evaluated are inadequate for needed protection of CIGS cells

Resolution: Dow internal developments in concert with outside suppliers have identified high potential approaches

Obstacle: Lack of patent waiver has interfered with DOE discussions

Resolution: Awaiting patent waiver



Barriers encountered or anticipated that may inhibit success of programs

1. CIGS protection is an issue
2. Code Approval for a new multi-functional product time consuming, expensive and idiosyncratic
3. Long Life testing takes a long time – liability concerns

Conclusion – Dow Chemical SAI TPP



1. Excellent progress has been made
2. All indications are we will meet LCOE Targets
3. Distributed rooftop PV is most effective use of PV for electricity generation
4. Challenges remain with respect to form factor options due to limited options on top sheet protection for CIGS
5. Alternative PV options remain and will be evaluated

Conclusion – Dow Chemical SAI TPP



**Goal: Large Scale (gigawatt) Cost
Effective Distributed Rooftop Electricity
Generation**

**Results: Feasibility is real, products in
development, pilot line operational
within 12 months**



Thank you for your attention

Dow Building Solutions
Global Solar Energy
Fronius
IBIS Associates
Lennar Corporation
Prost Builders, Inc
Pulte Homes, Inc.
University of Delaware - IEC
Southern California Edison

